ANNATH RAMALINGA MAHARAJAPA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE B

Name of work: Improvements and maintenance of culverts in Muthyalareddy Colony and surrounding Area in Ward no 19 Dasarahalli Sub Division

Sl No	Description of work	Unit	Qty	Estimated rate	
				In figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
	Earth work excation in normal mass for roads, drains & other works in ordinary soil including , excavated surface soil & lead up to 50m beyond the disposed earth to be included in the schedule of rates complete as per specification.	Cum	90.79	175.00	
	Providing Plain cement concrete of mix 1:3:6 with 40 mm graded granite metal (Coarse Aggregate) and fine aggregate @ 40 percent by volume of coarse aggregate in foundation, mechanically mixed, laid in layers not exceeding 150 mm thickness and compacted by vibration including curing for 14 days including cost of all materials, labour, TOM etc complete as per specifications.	Cum	13.62	4930.00	
	Providing and laying plain/reinforced cement concrete for side walls with M20 nominal mix concrete with OPC at 300 kgs per cum using graded granite metal/stone aggregates of 20 mm nominal size and fine aggregates at 0.43 cum machine mixed, including for walls and bottom including removing laitance, curing, M.S steel reinforcement for R.C.C work including cutting, bending, binding, placing in position, providing wherever required tying with binding wire and anchoring to the adjoining members where necessary complete as per design (laps, hooks and bends shall not be measured and paid) cost of materials, labour, TOM complete as per specifications.	Cum	55.73	4930.00	
		Tonne	5.02	55000.00	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division

Scanned by CamScanner